

Equipment Details/ उपकरण का विवरण

Equipment Details	
PCV-201	
Nabha BP delivery line Flow Control Valve	
FCV Details	
Make	REXA
Model	L2000-4-B-P-C6
S/N	C0702196-1-1
Rating	240 V, 2A
Operation Philosophy	ESD Valve
ESD Interlock	i-1,2,3,4,5,6,7,10,11
Installation Year	2008
Control Box & Valve Details	
Make	AKRON ELECTRIC INC.
CAT No.	CXJ242410 H3 N1 N4 N5 G8 5X9
Series	600#
Lube Oil	20W50
CPU CARD	X1A CPU

ESD Interlock for PCV ESD Operation		
S. No	NABHA ESD/ALARM INTERLOCK DETAILS	INTERLOCKS
1	ESD FROM MCC THROUGH SCADA	I-1
2	ESD FROM SCC & ESD PB @ PLC PANEL (ESD-204)	I-2
3	ESD FROM FIELD PUSH BUTTONS :	
	ESD -201 (NEAR SRB)	I-3
	ESD -202 (DELIVERY AREA)	
	ESD-203 (NEAR CONTROL ROOM)	
4	NABHA DELIVERY LINE PR. HI-HI : PS-202	I-4
5	NABHA DELIVERY LINE PR. LO-LO : PS-203	I-5
6	LPG STORAGE VESSELS LEVEL HI-HI	I-6
7	STATION INLET PRESSURE LO-LO : PS-201	I-7
8	STATION OUTLET PRESSURE LO-LO : PS-205	I-8
9	STATION OUTLET PRESSURE HI-HI : PS-204	I-9
10	ESD FROM MARKETING (Nabha BP)	I-10
11	ESD FROM PIPELINE ABNORMAL CONDITIONS	I-11

* For field location of PCV 201, refer process piping diagram on next page




Indian Oil

PANIPAT JALANDHAR LPG PIPELINE, NABHA DELIVERY STATION PROCESS PIPING



Indian Oil



LEGENDS:

GATE VALVE

BALL VALVE

GLOBE VALVE



MOTOR OPERATED VALVE



HAND OPERATED VALVE



PNEUMATIC VALVE



PRESSURE/FLOW CONTROL VALVE



NON RETURN VALVE



GAS DETECTOR



MASS FLOW METER



BASKET STRAINER



EHS WATER PUMP

➤ **Field Location of PCV-201 (Marked in red)**